MYSORE DIVISION.

ADVERTISEMENT.

The 27th June 1889.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 17th July 1889, for constructing a new Taluk Cutcherry at Nagamangala. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1891.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing a new Taluk Cutcherry at Nagamangala," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items.	Per.	Quantity.	Rate.
Earthwork excavation	C. Yd.	677	
Stone in chunam	C. Ft.	13,672	
Brick in chunam	Do	14,452	
Archwork	Do	690	
Stone slabs	Do	607	
Cornice work	R. Ft.	90	
Do	Do	110	
Do	Do	45	
Ornamental finials over wing	No.	4	
Teakwood work	C. ft.	463	
Roofing with Mangalore tiles and teak reepers	Sq.	55·14	
Do Bengal terrace	Do	18·48	
Do pucka do	Do	·89	
One course of bricks and 3″ concrete over covering slabs	Do	35·1	
Flooring with flag stones	C. Ft.	447	
Do concrete	Do	1,182	
Plastering	Sq.	227·80	
White washing	Do	150·99	
Color washing	Do	90·99	
Doors battened (teakwood)	S. Ft.	432	
Windows battened and glazed shutters with iron bars	Do	42	
Do glazed shutters	Do	147	
Do iron bars complete	Do	12	
Ventilators with iron bars	Do	65	
Sewers	Do	18	
Entrance gate	..	L. S.	
Pillars	..	L. S.	
Treasury gate	..	L. S.	
Painting chacolate	Sq.	16·13	
Composition to keep off white-ants	Do	23·00	
Wood oiling	Do	35·00	
Matting	Do	31·50	
Teakwood record racks	L. S.	L. S.	
Zinc gutters for roof	R. Ft.	64	
A. D. stone complete	..	L. S.	
Levelling ground and clearing site	..	L. S.	
Excavating ditch and planting hedge	..	L. S.	

V. H. KARVE, L. C. E.,
Executive Engineer.

2 D